

Fireplaces

Date: November 28, 2000

Revised: October 17, 2002

If you plan to build a fireplace on site, we can provide you with a rough opening in the wall and a cutout in the floor for your hearth. Dimensions and location at the time of order are necessary, a fireplace rough opening sheet must be completed and submitted with the order.

Pre-fabricated fireplaces already installed are available as an option. Units include screen, glass doors, fan and outside air intake.

The unit includes a gray slate surround and hearth, with a wood mantel.

Marble and Mantel options are available.

Wood and L.P or Natural Gas burning units are available.

1. Interior units will be finished to the ceiling of the first floor with the remaining parts shipped loose for field installation by builder.
2. Exterior units will be set in a 2' x 5' (approx) chase run to 1st floor ceiling height with the remaining parts and materials to complete the chase shipped loose for final installation in field by builder.
3. An exterior fireplace can only be built on the end of a module in the factory due to hauling restrictions. The total length of the module (including fireplace) cannot exceed 54'.
4. Corners and siding to complete the chase are included for exterior units.
5. Slate or Optional Marble surround is shipped loose, no adhesive will be shipped.
6. NAHC Mantel is installed, Optional Mantel or/ or T.V. Cabinet will be shipped loose.



**Heatilator Caliber 60
Direct Vent Gas Fireplace**



**Heatilator Novus 36
Top Direct Vent Gas Fireplace**



**Heatilator Woodburning
Fireplace**



Standard NAHC Mantel